

SZ-100-40M

Warranty

- ◆ 5 years Manufacturer Warranty
- ◆ Warranty on Electrical Performance: 10 years 90% + 25 years 80% of power output

Manufacturing

- ◆ Original cell sorting system ensures the best electric cell match
- ◆ EL-Testing before packing.
- ◆ Comprehensive module power testing.

Performance

- ◆ Higherer module efficiency and compact size. Weakened hot-spot effect) lower module failure
- ◆ rate and increased stability by shingle-tech.
- ◆ Special connection method lowers the internal resistance and ensures better performance than traditional connection with busbar.
- ◆ IP67 rated junction box) reliable cables and standard MC4 connectors improve the stability



Mechanical Data

Standard Test Conditions AM=1.5) E=1000W/m2) TC=25°C

Nominal Power	100W
Cell Type	Monocrystalline
Module Efficiency	19.67%
Maximum Power Current (Impp)	5.51A
Maximum Power Voltage (Vmpp)	18.15V
Open-circuit Voltage (Voc)	21.45V
Short-circuit Current (Isc)	5.9A
Maximum System Voltage	500V
Output Tolerance	± 3%
Cable	500mm / 2.5mm ²
Connector Type	MC4 / MC4 Compatible
Module Structure	Aluminum Frame / Glass / EVA / Backsheet
Junction box rating	≥ IP67
Diode	✓
Working Temperature	-40°C ~ +80°C

Packaging

Module Dimensions	1160*450*30mm
Module Weight	5.6kg
Package	Single Package
Pieces per Pallet	Free
Gross Weight per Pallet	Free
Pallet Dimensions	Free

SOLMAX NEW ENERGY B.V.

Address: Zonnebaan 23) 3542 EB Utrecht) the Netherlands

Email: info15@solarfam.nl

